

Estimate Abstract

**OD/358/3416/118742/423565/00072229 : CONSTRUCTION OF CC ROAD AT JHARKUSUMKHUNTI
Block : Kesinga, Gram Panchayat : Adhamunda
Created By:JALESWAR NAIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	20.7375	Cubic Meter	240.77592	4993.090641
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.775	Cubic Meter	517.527232	6611.4103888
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.4	Cubic Meter	5242.7055558	80737.66555932
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	7.75625	Cubic Meter	6789.5460886	52661.416849704
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	17.5	Square Meter	216.39264180804	3786.8712316407

Total Amount:	148790.45467046
----------------------	-----------------

Provision for Contingency (+) @	1487.9045467046
Display Citizen Board (+) @	2118

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	152396.35921717
----------------------	-----------------

Grand Net Total Amount	152396.35921716
-------------------------------	-----------------

JALESWAR NAIK
JE
Kesinga Block

ANANDA KUMAR MANDAL
AEE
Kesinga Block

JANMEJAYA SWAIN
BDO
Kesinga Block