

**Estimate Abstract**

**OD/361/3452/119466/385993/00068064 : CONS CC ROAD FROM ANIL HOUSE TO BIJAY GIRI HOUSE AT JAMUDIHA**

**Block : Kendujhar Sadar, Gram Panchayat : Palaspanga  
Created By:Ranjan Kumar Swain**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.14449215488	Cubic Meter	240.77592	997.89391152401
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.12625545216	Cubic Meter	1071.673832	9780.3691522272
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.89514794752	Cubic Meter	6076.20848404	126963.27523399
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	18.838600704	Cubic Meter	7531.27320948	141878.64878613
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	51.5054232	Square Meter	216.23489289764	11137.2696693
<b>Total Amount:</b>				290757.45675317
Provision for Contingency (+) @				3000

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	3242.54
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.99675317
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.99675317
-------------------------------	-----------------

**Ranjan Kumar Swain**  
**JE**  
**Kendujhar Sadar Block**

**Sabyasachi Pradhan**  
**AEE**  
**Kendujhar Sadar Block**

**Binod Chandra Panda**  
**BDO**  
**Kendujhar Sadar Block**