

Estimate Abstract

**OD/355/3393/118225/397783/00072805 : Construction of CC Road from Karapi Mian House to Abuli Mian House
Block : Tirtol, Gram Panchayat : Krushnandapur
Created By:PRASANT KUMAR PADHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0101a (Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift) : Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.			
	1.8	Cubic Meter	149.3184	268.77312
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	6.45	Cubic Meter	798.771832	5152.0783164
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.48	Cubic Meter	6775.74905228	64234.101015614
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	9	Cubic Meter	8222.32327736	74000.90949624
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	17.7	Square Meter	216.23489289764	3827.3576042882

Total Amount:	147483.21955254
----------------------	-----------------

Provision for Contingency (+) @	1474.8321955254
Display Citizen Board (+) @	1041

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	149999.05174807
----------------------	-----------------

Grand Net Total Amount	149999.05174807
-------------------------------	-----------------

PRASANT KUMAR PADHI
JE
Tirtol Block

SUCHISMITA BEHERA
AEE
Tirtol Block

Girija Sankar Mallick
BDO
Tirtol Block