

**Estimate Abstract**

**OD/363/3479/119913/429976/00067927 : Const. of Paver block road at Upper Goudaguda  
Block : Semiliguda, Gram Panchayat : Charangul  
Created By:SMT PREETIMAYEE PANIGRAHI**

| Sl No | Quantity   | Unit         | Rate in (Rs.) | Amount (Rs.)    |
|-------|--|--------------|---------------|-----------------|
| 1     | <b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge   |              |               |                 |
|       | 10.58  | Cubic Meter  | 240.77592     | 2547.4092336    |
| 2     | <b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.  |              |               |                 |
|       | 18   | Cubic Meter  | 586.560732    | 10558.093176    |
| 3     | <b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.   |              |               |                 |
|       | 10.58  | Cubic Meter  | 5555.2585903  | 58774.635885374 |
| 4     | <b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge. |              |               |                 |
|       | 330  | Square Meter | 624.1095      | 205956.135      |

|                      |                 |
|----------------------|-----------------|
| <b>Total Amount:</b> | 277836.27329497 |
|----------------------|-----------------|

|  |       |
|--|-------|
| Provision for Contingency (+) @                              | 3000  |
| Display Citizen Board (+) @                                  | 5000  |
| Any Other Lumpsum (+) @                                      | 14163 |
| Provision for survey investigation and quality control (+) @ |       |

|                      |                 |
|----------------------|-----------------|
| <b>Total Amount:</b> | 299999.27329497 |
|----------------------|-----------------|

|                               |                 |
|-------------------------------|-----------------|
| <b>Grand Net Total Amount</b> | 299999.27329497 |
|-------------------------------|-----------------|

**SMT PREETIMAYEE PANIGRAHI**  
**JE**  
Semiliguda Block

**ER TOPHAN KUMAR NAYAK**  
**AEE**  
Semiliguda Block

**JASHMIN KUMAR PRADHAN**  
**BDO**  
Semiliguda Block