

Estimate Abstract

**OD/353/3360/117492/413911/00070772 : Construction of CC Road at Pallav Sahi Ruamba
Block : Mohona, Gram Panchayat : Badasinghaba
Created By:Pradymna Kumar Nayak**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	21.6648	Cubic Meter	240.77592	5216.362151616
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.442	Cubic Meter	1019.901232	17789.117288544
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.0108	Cubic Meter	5646.52097022	135577.48571176
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	20.4	Square Meter	216.55039071844	4417.6279706562
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	18.615	Cubic Meter	7164.76437514	133372.08884323

Total Amount:	296372.68196581
----------------------	-----------------

Provision for Contingency (+) @	2963.7268196581
Display Citizen Board (+) @	663

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Total Amount:	299999.40878546
Grand Net Total Amount	299999.40878547

Pradymna Kumar Nayak
JE
Mohona Block

Narayan Padhy
AEE
Mohona Block

Rajiv Das
BDO
Mohona Block