

Estimate Abstract

**OD/361/3451/119435/385360/00071759 : MAINTENANCE OF BADKALIMATI PRIMARY SCHOOL
Block : Joda, Gram Panchayat : Badakalimati
Created By:DURGA MAHALI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.6439552	Cubic Meter	240.77592	1118.1525857188
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	0.766252608	Cubic Meter	1777.865832	1362.2943304441
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	0.766252608	Cubic Meter	6618.04658774	5071.0954577213
4	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	3.378477408	Cubic Meter	5497.066383032	18571.71458535
5	Masonry Brick Work : AR0603bi (Fourth Floor) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	5.89994403232	Cubic Meter	7173.3702044458	42322.482729342
6	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	54.26092618	Square Meter	187.3857176148	10167.722590683

7	Concrete : AR0318 (4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)) : 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (Old Work)			
	75.05075952	Square Meter	792.6043732722	59485.560212952
8	Painting : AR0901d (First Floor) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	230.2600855	Square Meter	73.602244926671	16947.659209807
9	Painting : AR0918f (Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)) : Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)			
	230.2600855	Square Meter	87.8957133375	20238.874468176

Total Amount:	175285.55617019
----------------------	-----------------

Provision for PH Work (+) @	21961
Provision for EI Work (+) @	
Provision for Contingency (+) @	1752.8555617019
Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.4117319
----------------------	----------------

Grand Net Total Amount	199999.41173189
-------------------------------	-----------------

DURGA MAHALI
JE
Joda Block

AJAYA KUMAR SAHOO
AEE
Joda Block

KendujharJodaBDO
BDO
Joda Block