

Estimate Abstract

**OD/346/3298/116061/393899/00071347 : R/R OF ROAD FROM RD ROAD THAKURANI TO NAYAK SAHI
Block : Bahanaga, Gram Panchayat : Ranapana
Created By:HAREKRUSHNA MARNDI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	0.7645536	Cubic Meter	240.77592	184.08609642931
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.36403584	Cubic Meter	1263.432432	4250.2319826664
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.12858944	Cubic Meter	5871.0961347	24239.345502947
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	3.36403584	Cubic Meter	7509.1087009	25260.910796283
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	8.89639128	Square Meter	216.23489289764	1923.7102156063

Total Amount:	55858.284593933
----------------------	-----------------

Provision for Contingency (+) @	558.58284593933
Display Citizen Board (+) @	2000

Any Other Lumpsum (+) @	1583
Provision for survey investigation and quality control (+) @	
Total Amount:	59999.867439872
Grand Net Total Amount	59999.867439872

HAREKRUSHNA MARNDI
JE
Bahanaga Block

Laxmikant Das
AEE
Bahanaga Block

Subhashree Tudu
BDO
Bahanaga Block