

Estimate Abstract

**OD/361/3446/119314/386942/00067528 : CONST OF CEMENT CONCRETE ROAD FROM GOBARDHAN JENA HOUSE TO PRAFULLA SHARMA HOUSE AT KOCHIANENDI
Block : Ghasipura, Gram Panchayat : Deogaon
Created By:Sasmita Hembram**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.75	Cubic Meter	240.77592	902.9097
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.25	Cubic Meter	978.652832	17860.414184
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	22	Cubic Meter	5850.14151724	128703.11337928
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	18.25	Cubic Meter	7334.94399588	133862.72792481
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	50	Square Meter	216.23489289764	10811.744644882
Total Amount:			292140.90983297	
Provision for Contingency (+) @				3000

Display Citizen Board (+) @	4000
Any Other Lumpsum (+) @	859
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.90983297
----------------------	-----------------

Grand Net Total Amount	299999.90983297
-------------------------------	-----------------

Sasmita Hembram
JE
Ghasipura Block

SWETAPADMA NANDA
AEE
Ghasipura Block

Binita Bijayeeni
BDO
Ghasipura Block