

**Estimate Abstract**

**OD/346/3299/116066/392691/00064142 : Completion of Mardaraj Community Center, Parikul, GP: Buanl  
Block : Baleshwar, Gram Panchayat : Buanl  
Created By:NIHARIKA MOHAPATRA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) :</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	30.26315225	Square Meter	173.266763914	5243.5984561942
2	<b>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) :</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	30.92276355	Square Meter	248.20128749	7675.0697258588
3	<b>Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) :</b> 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	12.9878394	Square Meter	190.534689676	2474.6339496407
4	<b>Plastering : AR1017 (20mm thick cement Plaster in CM (1:4) over masonry work in inside.) :</b> 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	13.285129	Square Meter	271.888540952	3612.0743401691
5	<b>Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) :</b> Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			
	13.285129	Square Meter	1528.540880726	20306.862782219
6	<b>Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) :</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	1.94228329216	Cubic Meter	5139.59283376	9982.5452895173

7	<b>Other Building Items. : AR1907 (aluminum sliding window (sliding type)) :</b> Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778,as windows frame, section No. 4095,4096 and 9777, 3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour, T&P etc. complete as per direction of Engineer-incharge.			
	0.6967725	Square Meter	4152.7950064027	2893.5533585987
8	<b>Other Building Items. : AR1911 (Stainless steel of 304 grade in hand railing using 50mm dia of 2mm) :</b> Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost,conveyance, taxes of all materials, labour,T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge			
	6.4960632	Meter	3129.0244276074	20326.340436081
9	<b>Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) :</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	74.18	Square Meter	71.84358555311	5329.3571763297
10	<b>Painting : AR0920 (Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)) :</b> Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	74.18	Square Meter	94.769140825	7029.9748663985
11	<b>Flooring : AR0817b (Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) ) :</b> Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	29.72896	Square Meter	880.589184194	26179.000633336
12	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	1.8689088	Cubic Meter	5998.8506307	11211.304733601
13	<b>Concrete : AR0307a (Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	1.41584	Cubic Meter	7313.8009609	10355.171952481

<b>Total Amount:</b>	132619.48770042
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	13380
Provision for Contingency (+) @	1500
Display Citizen Board (+) @	1000
Any Other Lumpsum (+) @	1500
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	149999.48770042
----------------------	-----------------

<b>Grand Net Total Amount</b>	149999.48770042
-------------------------------	-----------------

**NIHARIKA MOHAPATRA**  
**JE**  
**Baleshwar Block**

**PURUSOTTAM KARAN**  
**AEE**  
**Baleshwar Block**

**Uttam Kumar Jena**  
**BDO**  
**Baleshwar Block**