

Estimate Abstract

**OD/361/3452/119464/386024/00067361 : CONST. DRAIN AT DIMIRIDIHA GURUBA MAJHI HOUSE TO MUNA
MAJHI HOUSE
Block : Kendujhar Sadar, Gram Panchayat : Nuagaon
Created By:Ranjan Kumar Swain**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	70.792	Cubic Meter	240.77592	17045.00892864
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.344544	Cubic Meter	1053.089832	9840.6442710766
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.85198752	Cubic Meter	6088.79042774	175673.70543305
4	Concrete : AR0307 (First floor) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	5.715462912	Cubic Meter	7945.04595938	45409.615514972
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	1.07	Quintal	9267.2761797	9915.985512279
6	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	177.6769875	Square Meter	193.3193028232	34348.391351226

Total Amount:	292233.35101124
----------------------	-----------------

Display Citizen Board (+) @	4765.65
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	3000

Total Amount:	299999.00101124
----------------------	-----------------

Grand Net Total Amount	299999.00101124
-------------------------------	-----------------

Ranjan Kumar Swain
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block