

**Estimate Abstract**

**OD/353/3357/117451/414699/00067645 : Construction of paver block road from j.tarakeswar house to A.apparao house**

**Block : Gosani, Gram Panchayat : Machamara**

**Created By:ACHYUTANANDA MUDULI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	43.4	Cubic Meter	240.77592	10449.674928
2	<b>Road Work : AR1307 (Supplying &amp; spreading moorum and consolidation with HRR) :</b> Supplying & spreading moorum and consolidation with HRR including cost, conveyance, royalty, taxes cost of all labour & material, hire charges of T & P materials required for work as per specification and complete as per direction of Engineer-in-Charge.			
	24.5	Cubic Meter	1381.8212486784	33854.620592621
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.75	Cubic Meter	5524.33914922	53862.306704895
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	2.6	Cubic Meter	7037.21177814	18296.750623164
5	<b>Earth Work : AR0115a (Filling foundation and plinth with crusher dust well watered and rammed) :</b> Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.5	Cubic Meter	821.931132	20137.312734
6	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.25	Cubic Meter	954.150232	11688.340342

7	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	82.8	Square Meter	216.23489289764	17904.249131925
8	<b>miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) :</b> Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	241.5	Square Meter	635.028	153359.262

<b>Total Amount:</b>	319552.5170566
----------------------	----------------

Provision for Contingency (+) @	3195.525170566
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	2251
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	329999.04222717
----------------------	-----------------

<b>Grand Net Total Amount</b>	329999.04222717
-------------------------------	-----------------

**ACHYUTANANDA MUDULI**  
JE  
Gosani Block

**SASMITA KUMARI JENA**  
AEE  
Gosani Block

**GOURA CHANDRA PATNAIK**  
BDO  
Gosani Block