

Estimate Abstract

OD/369/3540/120956/409183/00068093 : CONSTRUCTION OF TARAPADA CC ROAD FROM TO LOKA BEHERA HOUSE

**Block : Kakat Pur, Gram Panchayat : Bangurigaon
Created By: BHAGYADHAR DHAL GPTA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	36.72	Cubic Meter	240.77592	8841.2917824
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.376	Cubic Meter	458.401832	13466.012216832
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	36.72	Cubic Meter	6354.68446194	233344.01344244
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	36.72	Square Meter	216.23489289764	7940.1452672013
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	29.376	Cubic Meter	7825.95881878	229895.36626048

Total Amount:	493486.82896935
----------------------	-----------------

Provision for Contingency (+) @	
---------------------------------	--

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	1513.17
Provision for survey investigation and quality control (+) @	

Total Amount:	499999.99896935
----------------------	-----------------

Grand Net Total Amount	499999.99896935
-------------------------------	-----------------

BHAGYADHAR DHAL GPTA
JE
Kakat Pur Block

K SNESHASHIS SUBUDHI AEE
AEE
Kakat Pur Block

PuriKakatPurBDO
BDO
Kakat Pur Block