

**Estimate Abstract**

**OD/353/3360/117493/413933/00070867 : Construction of CC Road with Drain at Jalibadi  
Block : Mohona, Gram Panchayat : Baghamari  
Created By:Pradymna Kumar Nayak**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	35.721	Cubic Meter	240.77592	8600.75663832
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.489	Cubic Meter	1085.652232	14644.362957448
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.715	Cubic Meter	5601.21029972	144035.1228573
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	84.4	Square Meter	216.39264180804	18263.538968599
5	<b>Plastering : AR1006 (12mm thick cement plaster (1:4) over brickwork in inside) :</b> 12mm thick cement plaster (1:4) over brickwork in inside with cement punning for skirting/wall punning including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc. comp. and as per direction of Engineer-in-charge.			
	72	Square Meter	197.7024923392	14234.579448422
6	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	13.115	Cubic Meter	7115.78205164	93323.481607259

<b>Total Amount:</b>	293101.84247735
----------------------	-----------------

Provision for Contingency (+) @	2931.0184247735
Display Citizen Board (+) @	3900
Any Other Lumpsum (+) @	67
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.86090212
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.86090212
-------------------------------	-----------------

**Pradymna Kumar Nayak**  
**JE**  
**Mohona Block**

**Narayan Padhy**  
**AEE**  
**Mohona Block**

**Rajiv Das**  
**BDO**  
**Mohona Block**