

Estimate Abstract

**OD/357/3405/118534/381149/00075605 : Construction of Drain at Goud Pada Bhounra
Block : Kirmira, Gram Panchayat : Bhimjore
Created By:Dhananjaya Kalo**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	111.24	Cubic Meter	240.77592	26783.9133408
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.248	Cubic Meter	631.758232	14055.357145536
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.832	Cubic Meter	5556.64025414	82416.088249404
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	296.64	Square Meter	216.23489289764	64143.918629156
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	34.26192	Cubic Meter	7007.75836418	240099.25645287

Total Amount:	427498.53381776
----------------------	-----------------

Display Citizen Board (+) @	1785
Any Other Lumpsum (+) @	

Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	4274.9853381776
Total Amount:	433558.51915594
Grand Net Total Amount	433558.51915594

Dhananjaya Kalo
JE
Kirmira Block

SAHADEV MUNDARI
AEE
Kirmira Block

Abinash Lakra
BDO
Kirmira Block