

Estimate Abstract

OD/373/3583/121676/384577/00067203 : Construction of Cement Concrete Road from Jhala House to Surendra House at Balanda
Block : Lathikata, Gram Panchayat : Balanda
Created By: MADHUSMITA SAHU

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	45.301	Cubic Meter	240.77592	10907.38995192
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	32.596	Cubic Meter	581.258232	18946.693330272
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	34.4994	Cubic Meter	5295.63406242	182696.19777305
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	33.4	Square Meter	216.39264180804	7227.5142363885
5	R.C.C. Work : AR0410a (Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height			
	5.76	Square Meter	663.29946175911	3820.6048997325
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	7.293995	Quintal	8443.1183613	61584.06311173

7	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	13.068	Cubic Meter	5487.6807955634	71713.012636423
8	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	31.651	Cubic Meter	6783.71151454	214711.25314671
9	R.C.C. Work : AR0410f (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor in ground floor R.C.C. walls and fins including attached pilasters			
	32.4	Square Meter	934.78613583205	30287.070800958

Total Amount:	601893.79988718
----------------------	-----------------

Provision for Contingency (+) @	6140
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	362
Provision for survey investigation and quality control (+) @	

Total Amount:	613395.79988718
----------------------	-----------------

Grand Net Total Amount	613395.79988718
-------------------------------	-----------------

MADHUSMITA SAHU
JE
Lathikata Block

LASA MARANDI
AEE
Lathikata Block

BDO LATHIKATA
BDO
Lathikata Block