

Estimate Abstract

**OD/358/3419/118809/422429/00064064 : Improvement of Road from Adenpada to Dangaghat
Block : Madanpur Rampur, Gram Panchayat : Alatar
Created By:JE BEPARI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.723102	Cubic Meter	240.77592	896.43330930384
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.417512	Cubic Meter	550.857232	11797.991376647
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	14.10811	Cubic Meter	5790.7234758	81696.163776169
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	12.474	Square Meter	216.39264180804	2699.2818139135
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	7.9716	Cubic Meter	7303.3128886	58219.089022764

Total Amount:	155308.9592988
----------------------	----------------

Provision for Contingency (+) @	1553.089592988
Display Citizen Board (+) @	3000

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	159862.04889178
----------------------	-----------------

Grand Net Total Amount	159862.04889179
-------------------------------	-----------------

JE BEPARI
JE
Madanpur Rampur Block

AEE MRAMPUR
AEE
Madanpur Rampur Block

Sharat Kumar Sethi
BDO
Madanpur Rampur Block