

Estimate Abstract

**OD/369/3540/120963/409343/00067957 : CONSTRUCTION OF CC ROAD FROM PWD ROAD TO BANA KANDI HOUSE VIA JOGESWARI TEMPLE, KURUJANGA
Block : Kakat Pur, Gram Panchayat : Kurujanga
Created By:AJAYA KUMAR JENA JE**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	93.6	Cubic Meter	240.77592	22536.626112
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	62.4	Cubic Meter	458.401832	28604.2743168
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	56.16	Cubic Meter	6354.68446194	356879.07938255
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	62.4	Square Meter	216.23489289764	13493.057316813
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	46.8	Cubic Meter	7825.95881878	366254.8727189

Total Amount:	787767.90984707
----------------------	-----------------

Provision for Contingency (+) @	
---------------------------------	--

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	7230
Provision for survey investigation and quality control (+) @	

Total Amount:	799997.90984707
----------------------	-----------------

Grand Net Total Amount	799997.90984707
-------------------------------	-----------------

AJAYA KUMAR JENA JE
JE
Kakat Pur Block

SANTOSH KUMAR SETHI
AEE
Kakat Pur Block

PuriKakatPurBDO
BDO
Kakat Pur Block