

Estimate Abstract

OD/363/3478/119905/430026/00069906 : Provision for paver block road at Kakipadu village.

Block : Pottangi, Gram Panchayat : Nuagaon

Created By: PRASANNA GARADA

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	12.6	Cubic Meter	240.77592	3033.776592
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.1	Cubic Meter	1320.275232	21256.4312352
3	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	10.5	Cubic Meter	7660.3563726	80433.7419123
4	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	280	Square Meter	645.903	180852.84
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	42	Square Meter	217.92263376324	9152.7506180561

Total Amount:	294729.54035756
----------------------	-----------------

Provision for Contingency (+) @	3000
---------------------------------	------

Display Citizen Board (+) @	2000
Any Other Lumpsum (+) @	270
Provision for survey investigation and quality control (+) @	0

Total Amount:	299999.54035756
----------------------	-----------------

Grand Net Total Amount	299999.54035756
-------------------------------	-----------------

PRASANNA GARADA
JE
Pottangi Block

ER TOPHAN KUMAR NAYAK
AEE
Pottangi Block

RAMKRISHNA NAYAK
BDO
Pottangi Block