

Estimate Abstract

OD/365/3507/120344/387886/00077294 : Const of CC road from PMGSY road to Bhantadhuli house in Harijon Sahi

**Block : Saraskana, Gram Panchayat : Bhursani
Created By:Binay Kumar Tiriya**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	7.6176	Cubic Meter	240.77592	1834.134648192
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.01	Cubic Meter	1090.793132	18554.39117532
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	28.8	Square Meter	216.23489289764	6227.564915452
4	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	33.5376	Cubic Meter	6046.5790493	202787.7495238
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	20.736	Cubic Meter	7778.0245541	161285.11715382

Total Amount:	390688.95741659
----------------------	-----------------

Provision for Contingency (+) @	4000
---------------------------------	------

Display Citizen Board (+) @	4000
Any Other Lumpsum (+) @	1311
Provision for survey investigation and quality control (+) @	

Total Amount:	399999.95741659
----------------------	-----------------

Grand Net Total Amount	399999.95741659
-------------------------------	-----------------

Binay Kumar Tiriya
JE
Saraskana Block

Gagan Bihari Mohanty
AEE
Saraskana Block

Suman Raja Mohanty
BDO
Saraskana Block