

Estimate Abstract

**OD/361/3452/119450/386041/00065749 : Construction of cc drain from kokila naik house to dhruba sethy house at Mukuna village under Bauripada GP
Block : Kendujhar Sadar, Gram Panchayat : Bauripada
Created By:Ratikanta Lenka**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	42.1353984	Cubic Meter	240.77592	10145.189314327
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.0225664	Cubic Meter	995.055232	6987.8414383874
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.0676992	Cubic Meter	5933.85007282	125012.56843207
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	2.387672576	Cubic Meter	7389.67119534	17644.11525877
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	99.99335696	Square Meter	216.23489289764	21622.052832721
6	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	49.99667848	Square Meter	249.854799294	12491.910066987

Total Amount:	193903.67734326
----------------------	-----------------

Display Citizen Board (+) @	4096.32
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	2000

Total Amount:	199999.99734326
----------------------	-----------------

Grand Net Total Amount	199999.99734326
-------------------------------	-----------------

Ratikanta Lenka
JE
Kendujhar Sadar Block

Sabyasachi Pradhan
AEE
Kendujhar Sadar Block

Binod Chandra Panda
BDO
Kendujhar Sadar Block