

Estimate Abstract

**OD/346/3305/116242/393112/00068331 : Const of market complex at Mardarajpur Chhak
Block : Nilgiri, Gram Panchayat : K.P.Lakharaj
Created By:BAIDYANATH SINGH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	13.748372736	Cubic Meter	240.77592	3310.2770940133
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	12.475870593642	Cubic Meter	987.278232	12317.155462352
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	5.0026543845984	Cubic Meter	6296.62646226	31499.845979603
4	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	1.3858087876608	Cubic Meter	5196.656602368	7201.5723860171
5	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	11.18916972816	Cubic Meter	6462.1097143202	72305.64239552
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	20.60216928	Square Meter	216.23489289764	4454.9078677198

7	R.C.C. Work : AR0410d (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm			
	25.455886515	Square Meter	1047.3822930467	26662.044789617
8	R.C.C. Work : AR0410e (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm			
	7.525143	Square Meter	499.15267251462	3756.1952395047
9	R.C.C. Work : AR0410a (Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height			
	36.116505765	Square Meter	662.689943368	23934.045160058
10	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	11	Quintal	8657.3179493	95230.4974423
11	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	13.61243510592	Cubic Meter	5229.986602368	71192.853229565
12	Plastering : AR1017 (20mm thick cement Plaster in CM (1:4) over masonry work in inside.) : 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	36.116505765	Square Meter	273.5759198336	9880.6062858354
13	Plastering : AR1004 (12mm thick cement plster (1:6) over Brick work in inside) : 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	74.54629623	Square Meter	174.0884909452	12977.652216235
14	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			

223.6639725	Square Meter	249.188244542	55734.432674565	
15	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	30.0468926466	Square Meter	191.3723797168	5750.1453488751
16	Flooring : AR0802ii (2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.			
	27.52251375	Square Meter	376.1514947452	10352.634686208
17	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	4.695	Quintal	15989.305373087	75069.788726643
18	Painting : AR0903a (Painting two coats of enamel paint with a coat of wood primer in inner surface paint (Inside)) : Painting two coats of enamel paint with a coat of wood primer in inner surface paint including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)			
	19.99737075	Square Meter	234.34919434323	4686.3677242454
19	Painting : AR0920a (Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat oil bound Primer on new work (Inside)) : Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat oil bound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	253.71066076	Square Meter	163.77808061851	41552.245051727
20	Painting : AR0918g (Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside)) : Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)			
	74.54629623	Square Meter	156.89114311851	11695.653630776

Total Amount:	579564.56339138
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	9435.43
Provision for Contingency (+) @	6000

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	599999.99339138
----------------------	-----------------

Grand Net Total Amount	599999.99339138
-------------------------------	-----------------

BAIDYANATH SINGH
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block