

Estimate Abstract

**OD/354/3374/117767/412284/00072164 : Construction of CC Paver Road from Khandra Nua Sahi to Dasa Sahi
Block : Hinjilicut, Gram Panchayat : Chandali
Created By:DURYODHAN BEHERA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	8.25	Cubic Meter	240.77592	1986.40134
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.05	Cubic Meter	804.488432	22565.9005176
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	10.12	Cubic Meter	5667.8584807	57358.727824684
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	49.5	Square Meter	216.39264180804	10711.435769498
5	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	165	Square Meter	630.5826	104046.129

Total Amount:	196668.59445178
----------------------	-----------------

Provision for Contingency (+) @	2000
---------------------------------	------

Display Citizen Board (+) @	1331
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	199999.59445178
----------------------	-----------------

Grand Net Total Amount	199999.59445178
-------------------------------	-----------------

DURYODHAN BEHERA
JE
Hinjilicut Block

SAHADEB PRADHAN
AEE
Hinjilicut Block

Sushree Sagarika Sarangi
BDO
Hinjilicut Block