

Estimate Abstract

**OD/361/3449/119391/387096/00075357 : CONST OF CC ROAD AT JHANAJHANA
Block : Hatadihi, Gram Panchayat : Dhenka
Created By:PRAFULLA CHANDRA BEHERA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	19.01225	Cubic Meter	240.77592	4577.69198502
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.64725	Cubic Meter	912.901832	14284.403190762
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	27.9295	Cubic Meter	5944.87189982	166037.29972602
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	26.92	Square Meter	216.39264180804	5825.2899174724
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	18.423375	Cubic Meter	7386.99701834	136093.41619276

Total Amount:	326818.10101204
----------------------	-----------------

Provision for Contingency (+) @	3268.1810101204
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	2913
Provision for survey investigation and quality control (+) @	
Total Amount:	337999.28202216
Grand Net Total Amount	337999.28202216

PRAFULLA CHANDRA BEHERA
JE
Hatadihi Block

MADAN MOHAN BEHERA
AEE
Hatadihi Block

RANJAN KUMAR PARIDA
BDO
Hatadihi Block