

Estimate Abstract

**OD/353/3360/117497/413673/00071626 : Constriction of CC Road at Ratha Danda to Shiva mandir
Block : Mohona, Gram Panchayat : Chudangapur
Created By:Subham Chandan Sabat**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.907	Cubic Meter	1085.652232	18355.122286424
2	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.564	Cubic Meter	5809.10876032	119458.51254722
3	Earth Work : AR0103aa (Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m) : Earthwork in stoney earth and gravels mixed with stone and boulder not exceeding 0.014cum in volume in foundation and plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layer not exceeding 0.3m in depth and as per specification approved by the department			
	29.0175	Cubic Meter	375.4984464	10896.026168412
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	10.6	Square Meter	216.39264180804	2293.7620031652
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	19.345	Cubic Meter	7319.45382384	141594.83422218

Total Amount:	292598.25722741
----------------------	-----------------

Provision for Contingency (+) @	2925.9825722741
---------------------------------	-----------------

Display Citizen Board (+) @	4475
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.23979968
----------------------	-----------------

Grand Net Total Amount	299999.23979968
-------------------------------	-----------------

Subham Chandan Sabat
JE
Mohona Block

Narayan Padhy
AEE
Mohona Block

Rajiv Das
BDO
Mohona Block