

Estimate Abstract

**OD/365/3498/120220/388888/00069111 : CONSTRUCTION OF DRAINAGE SYSTEM AT MENDHASINGA
SALARAPADA**

**Block : Karanjia, Gram Panchayat : Batpalsa
Created By:Mitalin Dhal**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	71.6981376	Cubic Meter	240.77592	17263.185042927
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.886795136	Cubic Meter	1143.818132	9021.0592799262
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	35.8490688	Cubic Meter	6017.7056238	215729.14292575
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	3.823900672	Cubic Meter	7568.4872776	28941.143586838
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	156.820264	Square Meter	216.23489289764	33910.01299022
6	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	78.410132	Square Meter	195.543960214	15332.627732182

Total Amount:	320197.17155785
----------------------	-----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	183
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	3201.9717155785

Total Amount:	328582.14327342
----------------------	-----------------

Grand Net Total Amount	328582.14327343
-------------------------------	-----------------

Mitalin Dhal
JE
Karanjia Block

LOKANATH NAIK
AEE
Karanjia Block

PRADYUMNA KUMAR NAYAK
BDO
Karanjia Block