

**Estimate Abstract**

**OD/346/3307/116290/392875/00072735 : Const of CC Road from Baida Chhaka to Uday Das House VillSrirampur  
Block : Remuna, Gram Panchayat : Srijang  
Created By:DHARMENDRA JENA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.85	Cubic Meter	240.77592	1408.539132
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.74	Cubic Meter	1327.183632	34161.70668768
3	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	20.475	Cubic Meter	7790.16041312	159503.53445863
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	71.5	Square Meter	216.39264180804	15472.073889275
5	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.91	Cubic Meter	6161.98654376	165819.05789258

<b>Total Amount:</b>	376364.91206017
----------------------	-----------------

Provision for Contingency (+) @	4000
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	14635
Provision for survey investigation and quality control (+) @	
<b>Total Amount:</b>	399999.91206017
<b>Grand Net Total Amount</b>	399999.91206017

**DHARMENDRA JENA**  
**JE**  
**Remuna Block**

**AJAY KUMAR BEHERA**  
**AEE**  
**Remuna Block**

**Sourav Sarthak Mohapatra**  
**BDO**  
**Remuna Block**