

Estimate Abstract

**OD/346/3307/116290/392876/00072736 : Const of Drain from Parshuram Jena house to Dhalagadi
VillMahamadabad GPSrijung
Block : Remuna, Gram Panchayat : Srijang
Created By:DHARMENDRA JENA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	26.25	Cubic Meter	240.77592	6320.3679
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.5	Cubic Meter	1327.183632	4645.142712
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.5	Cubic Meter	6149.36235176	21522.76823116
4	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	14	Cubic Meter	6505.0571681352	91070.800353893
5	R.C.C. Work : AR0410e (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm			
	150	Square Meter	499.57698698128	74936.548047192
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	6.3	Quintal	8638.4039318	54421.94477034

7	miscellaneous : ARM260 (Laying and fixing in position R.C.C. spun pipes with collars jointed with cement mortar 1:3 complete excluding cost of spun pipes and collars 450mm dia R.C.C. pipe. (Other miscellaneous items) and as directed by Engineer-in-Charge.) : Laying and fixing in position R.C.C. spun pipes with collars jointed with cement mortar 1:3 complete excluding cost of spun pipes and collars 450mm dia R.C.C. pipe. (Other miscellaneous items) and as directed by Engineer-in-Charge.			
	72	Meter	30.32	2183.04

Total Amount:	255100.61201458
----------------------	-----------------

Provision for PH Work (+) @	1
Provision for EI Work (+) @	1
Provision for Contingency (+) @	3000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	36897
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.61201458
----------------------	-----------------

Grand Net Total Amount	299999.61201458
-------------------------------	-----------------

DHARMENDRA JENA
JE
Remuna Block

AJAY KUMAR BEHERA
AEE
Remuna Block

Sourav Sarthak Mohapatra
BDO
Remuna Block