

Estimate Abstract

**OD/350/3337/116959/907097/00071215 : "CONST OF CC ROAD FROM NH 55 TO AJAYA ROUT HOUSE, "
Block : Cuttacksadar, Gram Panchayat : Fakirapada
Created By:SAMAPEEKA NAYAK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	8.6967972	Cubic Meter	240.77592	2093.9793468834
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	26.167696464	Cubic Meter	525.607232	13753.930506259
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	31.30846992	Cubic Meter	6060.21693386	189736.11958243
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	22.41841056	Cubic Meter	7524.48725582	168687.04455446
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	90.79781802	Square Meter	216.23489289764	19633.656454894

Total Amount:	393904.73044493
----------------------	-----------------

Provision for Contingency (+) @	4000
Display Citizen Board (+) @	2000

Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	399904.73044493
----------------------	-----------------

Grand Net Total Amount	399904.73044493
-------------------------------	-----------------

SAMAPEEKA NAYAK
JE
Cuttacksadar Block

SUBHASMITA NATH
AEE
Cuttacksadar Block

PRATIK SAHOO
BDO
Cuttacksadar Block