

Estimate Abstract

**OD/364/3482/119980/430254/00079026 : Water Supply at Pakanaguda School and Market Complex under 5th SFC Devolution fund for the year 23-24
Block : Korukonda, Gram Panchayat : Tarlakotta
Created By:RUPAK KUMAR SINGH SAMANT**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	1.1475	Cubic Meter	240.77592	276.2903682
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	0.432	Cubic Meter	703.569232	303.941908224
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	0.46575	Cubic Meter	5332.9223514	2483.8085851645
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	1.07769	Cubic Meter	6822.2314258	7352.2505852704
5	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	12.6585	Square Meter	188.649669712	2388.0218440494
6	Plastering : AR1006 (12mm thick cement plaster (1:4) over brickwork in inside) : 12mm thick cement plaster (1:4) over brickwork in inside with cement punning for skirting/wall punning including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc. comp. and as per direction of Engineer-in-charge.			
	12.65	Square Meter	189.472204824	2396.8233910236

7	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	9.045	Square Meter	216.39264180804	1957.2714451537

Total Amount:	17158.408127086
----------------------	-----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	373841
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	4000

Total Amount:	399999.40812709
----------------------	-----------------

Grand Net Total Amount	399999.40812709
-------------------------------	-----------------

RUPAK KUMAR SINGH SAMANT
JE
Korukonda Block

SUKANTA KUMAR SWAIN
AEE
Korukonda Block

MalkangiriKorukondaBDO
BDO
Korukonda Block