

Estimate Abstract

**OD/370/3550/121146/426749/00074067 : Construction of CC road and drain at Mill Sahi to Nala
Block : Gunupur, Gram Panchayat : Dombosora
Created By:HIMANSU BHUSAN RATH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	103.726	Cubic Meter	240.77592	24974.72307792
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.628	Cubic Meter	596.408232	10513.484313696
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	170	Square Meter	216.23489289764	36759.931792599
4	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	5.852	Quintal	8652.9234393	50636.907966784
5	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.935	Cubic Meter	5132.38230842	112578.80593519
6	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	20.898	Cubic Meter	5597.9854629834	116986.70020543

7	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specificaion and direction of Engineer-in charge.			
	5.18	Cubic Meter	6871.86047654	35596.237268477

Total Amount:	388046.7905601
----------------------	----------------

Provision for Contingency (+) @	4000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	2952
Provision for survey investigation and quality control (+) @	

Total Amount:	399998.7905601
----------------------	----------------

Grand Net Total Amount	399998.7905601
-------------------------------	----------------

HIMANSU BHUSAN RATH
JE
Gunupur Block

HARI KRISHNA PANDA
AEE
Gunupur Block

SRI SWASTIK JAMADAR
BDO
Gunupur Block