

Estimate Abstract

**OD/373/3587/121753/384026/00070188 : Construction of Cultural Centre at Tangargaon Nawatoli
Block : Subdega, Gram Panchayat : Tangargaon
Created By: JAYA KUMAR KISAN**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	20.475	Cubic Meter	240.77592	4929.886962
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.96806	Cubic Meter	662.159232	13884.19450613
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.14789	Cubic Meter	5984.63064072	48762.112151216
4	Masonry Brick Work : AR0603c (Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	10.18125	Cubic Meter	5049.265295296	51407.832287732
5	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	18.99005	Cubic Meter	6138.3937592744	116568.40440831
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	19	Quintal	8679.3593712	164907.8280528

7	Masonry Brick Work : AR0603ci (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.		
	12.81215	Cubic Meter	5082.595295296
8	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.		
	85.973	Square Meter	168.6504397744
9	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.		
	65.325	Square Meter	242.661956024
10	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc		
	10.08	Square Meter	216.23489289764
11	R.C.C. Work : AR0410e (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm		
	16.752	Square Meter	499.15267251462
12	R.C.C. Work : AR0410d (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, girder and bressmer, etc. Data for 4.2sqm		
	35.498	Square Meter	1047.3822930467
13	R.C.C. Work : AR0410a (Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height		
	71.5818	Square Meter	662.689943368
14	Other Building Items. : AR1901Ba (Vitrified Tile 600mmx600mm Coloured /Printed) : Supplying, fitting & fixing Vitrified Tile 600mmx600mm Coloured /Printed series(Homogeneous) in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all work all materials, taxes, labor, T&P , etc. complete as per direction of Engineer-in-charge.		

47.07	Square Meter	1051.2772890502	49483.621995593
15	Flooring : AR0817ab (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) : Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm Coloured /Printed series(Homogeneous) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.		
	15.945	Square Meter	1572.019908247
16	Other Building Items. : AR1902 (cement based wall putty (water based)) : Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.		
	110.32	Square Meter	79.21834
17	Painting : AR0918cb (Finishing wall two coats with weather coat with one coat waterbound Primer) : Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)		
	85.96	Square Meter	160.74632751492
18	Painting : AR0920b (Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work (Inside)) : Finishing wall surface with two coats with plastic emulsion paint of approved shades above one coat waterbound Primer on new work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)		
	110.32	Square Meter	166.61523623821
19	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.		
	2.83725	Quintal	16010.220251087
20	Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.		
	10.5375	Square Meter	230.30528032053
21	Concrete : AR0317 (2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips) : 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge. (new work)		
	55.8376	Square Meter	358.0521573044

Total Amount:	774420.68344778
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	4579
Provision for Contingency (+) @	8000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	8000
Provision for survey investigation and quality control (+) @	

Total Amount:	799999.68344778
----------------------	-----------------

Grand Net Total Amount	799999.68344778
-------------------------------	-----------------

JAYA KUMAR KISAN
JE
Subdega Block

BINAY BHUSHAN DASH
AEE
Subdega Block

BDO Subdega
BDO
Subdega Block