

Estimate Abstract

OD/369/3540/120955/409299/00068110 : CONSTRUCTION OF CC ROAD FROM KANTIMALA VILLAGE ROAD TO BALASAHU

Block : Kakat Pur, Gram Panchayat : Abadan

Created By: BHAGYADHAR DHAL GPTA

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.808	Cubic Meter	458.401832	13664.041808256
2	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	37.26	Cubic Meter	6293.03133696	234478.34761513
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	44.712	Square Meter	216.23489289764	9668.2945312393
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	29.808	Cubic Meter	7738.99829752	230684.06125248

Total Amount:	488494.7452071
----------------------	----------------

Provision for Contingency (+) @	5000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	1505.25
Provision for survey investigation and quality control (+) @	

Total Amount:	499999.9952071
----------------------	----------------

Grand Net Total Amount	499999.9952071
-------------------------------	----------------

BHAGYADHAR DHAL GPTA
JE
Kakat Pur Block

SANTOSH KUMAR SETHI
AEE
Kakat Pur Block

PuriKakatPurBDO
BDO
Kakat Pur Block