

Estimate Abstract

**OD/365/3500/120254/389247/00077412 : Construction of CC road from Sitala Mandap road to Kamta RD Road
Block : Kuliana, Gram Panchayat : Kuliana
Created By:SRIMANTA SETHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	8.865	Cubic Meter	240.77592	2134.4785308
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	30.099375	Cubic Meter	1089.884132	32804.831195617
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	40.998125	Cubic Meter	6283.5092428	257612.09737497
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	23.26875	Cubic Meter	7804.6710306	181604.93904327
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	63.75	Square Meter	216.23489289764	13784.974422225

Total Amount:	487941.32056689
----------------------	-----------------

Provision for Contingency (+) @	5000
Display Citizen Board (+) @	4000

Any Other Lumpsum (+) @	3058.67
Provision for survey investigation and quality control (+) @	
Total Amount:	499999.99056689
Grand Net Total Amount	499999.99056689

SRIMANTA SETHI
JE
Kuliana Block

PAPU BHUYAN
AEE
Kuliana Block

Jitendra Murmu
BDO
Kuliana Block