

Estimate Abstract

**OD/370/3557/121264/426561/00071322 : Construction of canal at Karubai
Block : Rayagada, Gram Panchayat : Karubai
Created By:SWAGATIKA CHHUAL SINGH**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	16.95	Cubic Meter	240.77592	4081.151844
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.6275	Cubic Meter	795.852932	6070.36823883
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.6275	Cubic Meter	5463.16745892	41670.309792912
4	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	12.7125	Cubic Meter	5768.2212341684	73328.512439366
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	5.842	Quintal	8659.2281118	50587.210629136
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	101.7	Square Meter	216.23489289764	21991.08860769

Total Amount:	197728.64155193
----------------------	-----------------

Display Citizen Board (+) @	2331.9
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	1977.2864155193

Total Amount:	202037.82796745
----------------------	-----------------

Grand Net Total Amount	202037.82796745
-------------------------------	-----------------

SWAGATIKA CHHUAL SINGH
JE
Rayagada Block

SAMEER KUMAR RATH
AEE
Rayagada Block

SHRI SUJIT KUMAR MISHRA
BDO
Rayagada Block