

Estimate Abstract

**OD/361/3451/119448/385353/00079336 : CONSTRUCTION OF CC ROAD FROM MAIN ROAD TO UP SCHOOL AT
NAMIRA
Block : Joda, Gram Panchayat : Palasa
Created By:DURGA MAHALI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	3.696	Cubic Meter	240.77592	889.90780032
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	16.863	Cubic Meter	1777.865832	29980.151525016
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.559	Cubic Meter	6581.58418182	135310.78919404
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	14.83944	Cubic Meter	8232.86131234	122171.05147279
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	18.48	Square Meter	216.23489289764	3996.0208207484
Total Amount:				292347.92081291
Provision for Contingency (+) @				2923.4792081291

Display Citizen Board (+) @	4728
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.40002104
----------------------	-----------------

Grand Net Total Amount	299999.40002104
-------------------------------	-----------------

DURGA MAHALI
JE
Joda Block

AJAYA KUMAR SAHOO
AEE
Joda Block

KendujharJodaBDO
BDO
Joda Block