

Estimate Abstract

**OD/365/3498/120226/388895/00067077 : Construction of C.C. Road from Bindhani house to Raghu house
Mirginendi
Block : Karanjia, Gram Panchayat : Miriginendi
Created By:RADHAGOBINDA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	22.08978125	Cubic Meter	240.77592	5318.6874030675
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.062125	Cubic Meter	1143.818132	21803.604209451
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.66765625	Cubic Meter	5865.5062493	115360.76064346
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	20.8	Square Meter	216.39264180804	4500.9669496072
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	18.98	Cubic Meter	7608.2688041	144404.94190182

Total Amount:	291388.9611074
----------------------	----------------

Provision for Contingency (+) @	2913.889611074
---------------------------------	----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	697.14
Provision for survey investigation and quality control (+) @	

Total Amount:	299999.99071848
----------------------	-----------------

Grand Net Total Amount	299999.99071847
-------------------------------	-----------------

RADHAGOBINDA
JE
Karanjia Block

LOKANATH NAIK
AEE
Karanjia Block

PRADYUMNA KUMAR NAYAK
BDO
Karanjia Block