

**Estimate Abstract**

**OD/369/3541/120986/410130/00075168 : CONST. OF MARUTI MANDAP AT TIGIRIA  
Block : Kanas, Gram Panchayat : Khandahota  
Created By:GOPINATH PALAI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>R.C.C. Work : AR0404Ac (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)			
	1.1704466112	Cubic Meter	14346.306002001	16791.58524328
2	<b>R.C.C. Work : AR0404Ad (Second Floor) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)			
	0.893111872	Cubic Meter	16289.014490793	14547.912224907
3	<b>R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips) :</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	5.6100111488	Cubic Meter	12605.889744315	70719.182006151
4	<b>Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) :</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	14.8002285888	Cubic Meter	5384.584328928	79693.078923805
5	<b>R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) :</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	8	Quintal	7959.7534905	63678.027924

6	<b>Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) :</b> Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	31.215408	Square Meter	1012.7526641606	31613.48761486
7	<b>Iron Work : AR1704 (Iron Doors and windows fixing) :</b> Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	1	Quintal	15324.881317087	15324.881317087

<b>Total Amount:</b>	292368.15525409
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	3000
Display Citizen Board (+) @	4631
Any Other Lumpsum (+) @	
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.15525409
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.15525409
-------------------------------	-----------------

**GOPINATH PALAI**  
JE  
Kanas Block

**SASWAT KUMAR SENAPATI**  
AEE  
Kanas Block

**SOUMYA RANJAN SWAIN**  
BDO  
Kanas Block