

Estimate Abstract

**OD/370/3551/121161/425545/00073188 : Const. of Bathing Ghat with changing room at Tadijhol
Block : Kalyansingpur, Gram Panchayat : Dhamunipanga
Created By:SIBA SHANKAR HEMBRAM**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	15.0165	Cubic Meter	240.77592	3615.61160268
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.9425	Cubic Meter	525.607232	2597.81374416
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	15.204	Cubic Meter	5623.97794192	85506.960628952
4	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	33.66	Square Meter	167.9844077984	5654.3551664941
5	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	28.512	Square Meter	241.864262064	6896.0338399688
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	48.405	Square Meter	216.39264180804	10474.485826718

7	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	0.5	Quintal	8646.6187668	4323.3093834
8	Painting : AR0901a (Priming one coat in inner surface with primer of approved quality over woodwork) : Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	54.192	Square Meter	70.08994432871	3798.3142630615
9	Painting : AR0919 (Finishing wall One Coat with plastic emulsion paint of approved shades on old work (Inside)) : Finishing wall One Coat with plastic emulsion paint of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)			
	54.192	Square Meter	61.22776449	3318.0550132421
10	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	8.64	Cubic Meter	7178.38805304	62021.272778266
11	Flooring : AR0802ii (2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.			
	5.8464	Square Meter	361.5657042984	2113.8577336102
12	R.C.C. Work : AR0404B (Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips.(Nominal mix as per IS-456, Table-9).) : R.C.C. work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge(Nominal mix as per IS-456, Table-9).			
	0.45954	Cubic Meter	5903.0521567984	2712.6885881351
13	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	4.9725	Cubic Meter	5238.957956456	26050.718438477

14	Masonry Brick Work : AR0603bi (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	6.35904	Cubic Meter	5272.287956456	33526.690006622
15	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	0.972	Quintal	15979.038723087	15531.625638841
16	Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) : Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.			
	6.48	Square Meter	230.35420628603	1492.6952567335

Total Amount:	269634.48790936
----------------------	-----------------

Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	17669
Provision for survey investigation and quality control (+) @	5000
Provision for Contingency (+) @	2696.3448790936

Total Amount:	299999.83278845
----------------------	-----------------

Grand Net Total Amount	299999.83278845
-------------------------------	-----------------

SIBA SHANKAR HEMBRAM
JE
Kalyansingpur Block

AEE
Kalyansingpur Block

MANISHA DAS
BDO
Kalyansingpur Block