

Estimate Abstract

**OD/363/3475/119855/428870/00071837 : Const. of CC drain at Nisanimunda to Ganasal at Charada
Block : Laxmipur, Gram Panchayat : Bhtaragada
Created By:RANJIT KHOSLA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	22.05	Cubic Meter	240.77592	5309.109036
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.205	Cubic Meter	718.820232	1584.99861156
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.76	Cubic Meter	5420.91496944	63749.960040614
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	1.8375	Cubic Meter	6922.93625128	12720.895361727
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	49	Square Meter	216.42213566644	10604.684647656

Total Amount:	93969.647697557
----------------------	-----------------

Display Citizen Board (+) @	5090
Any Other Lumpsum (+) @	

Provision for survey investigation and quality control (+) @	
Provision for Contingency (+) @	939.69647697557
Total Amount:	99999.344174533
Grand Net Total Amount	99999.344174533

RANJIT KHOSLA
JE
Laxmipur Block

AEE
Laxmipur Block

SABYASACHI BEHERA
BDO
Laxmipur Block