

**Estimate Abstract**

**OD/365/3498/120222/388832/00067314 : Construction of CC Road at Kalha- Karanjia Tumbasahi  
Block : Karanjia, Gram Panchayat : Dori  
Created By:RADHAGOBINDA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	36.83353125	Cubic Meter	240.77592	8868.6273735675
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	36.730875	Cubic Meter	854.513732	31387.037075875
3	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	36.75140625	Cubic Meter	5619.648484	206529.98441768
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	34.8	Square Meter	216.39264180804	7530.4639349198
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	31.755	Cubic Meter	7386.882147	234570.44257798

<b>Total Amount:</b>	488886.55538003
----------------------	-----------------

Provision for Contingency (+) @	5000
Display Citizen Board (+) @	5000

Any Other Lumpsum (+) @	1113.43
Provision for survey investigation and quality control (+) @	
<b>Total Amount:</b>	499999.98538003
<b>Grand Net Total Amount</b>	499999.98538003

**RADHAGOBINDA**  
**JE**  
**Karanjia Block**

**LOKANATH NAIK**  
**AEE**  
**Karanjia Block**

**PRADYUMNA KUMAR NAYAK**  
**BDO**  
**Karanjia Block**