

Estimate Abstract

**OD/357/3406/118542/381250/00077285 : Repair & maintenance of Toilet & Urinal with running water supply and Boundary of Govt. PS HS Kolabira
Block : Kolabira, Gram Panchayat : Kolabira
Created By:Harisankar Chhura**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	18.36	Cubic Meter	240.77592	4420.6458912
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.06	Cubic Meter	683.126832	2090.36810592
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.55	Cubic Meter	5433.86697714	13856.360791707
4	Masonry Brick Work : AR0603c (Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	11.475	Cubic Meter	4984.472285952	57196.819481299
5	Masonry Brick Work : AR0603ci (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	19.4049375	Cubic Meter	5017.802285952	97370.139746256
6	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	112.2	Square Meter	242.787561038	27240.764348464

7	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	81.6	Square Meter	168.7562664028	13770.511338468
8	Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) : Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.			
	163.2	Square Meter	71.83753306751	11723.885396618
9	Painting : AR0918Ai (Finishing wall one coat with weather coat) : Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.			
	163.2	Square Meter	57.09560199	9318.002244768

Total Amount:	236987.4973447
----------------------	----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	4032.4
Provision for Contingency (+) @	2480
Display Citizen Board (+) @	2000
Any Other Lumpsum (+) @	2500
Provision for survey investigation and quality control (+) @	

Total Amount:	247999.8973447
----------------------	----------------

Grand Net Total Amount	247999.8973447
-------------------------------	----------------

Harisankar Chhura
JE
Kolabira Block

MADHUMITA PAUL
AEE
Kolabira Block

Ashok Kumar Majhi
BDO
Kolabira Block