

**Estimate Abstract**

**OD/361/3451/119434/385311/00077304 : INSTALLATION OF GYM AND PLAY EQUIPMENT RURAL KHELPAIDIA**  
**Block : Joda, Gram Panchayat : Anseikala**  
**Created By:Kartikeswar Naik**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	14.0292	Cubic Meter	240.77592	3377.893536864
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	22.83138	Cubic Meter	1777.865832	40591.130399408
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	3.1176	Cubic Meter	6863.98018182	21399.144614842
4	<b>Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) :</b> Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm <sup>2</sup> with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	15.8524	Cubic Meter	5486.366497976	86972.076272515
5	<b>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) :</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	12.768	Square Meter	264.461772794	3376.6479150338
6	<b>Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) :</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	18.848	Square Meter	186.8156939764	3521.1022000672

<b>Total Amount:</b>	159237.99493873
----------------------	-----------------

Provision for PH Work (+) @	
Provision for EI Work (+) @	
Provision for Contingency (+) @	4000
Display Citizen Board (+) @	5000
Any Other Lumpsum (+) @	231762
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	399999.99493873
----------------------	-----------------

<b>Grand Net Total Amount</b>	399999.99493873
-------------------------------	-----------------

**Kartikeswar Naik**  
**JE**  
**Joda Block**

**AJAYA KUMAR SAHOO**  
**AEE**  
**Joda Block**

**KendujharJodaBDO**  
**BDO**  
**Joda Block**