

**Estimate Abstract**

**OD/361/3453/119483/385767/00069289 : Const. of CC Road from Mania Bandha to Jogeswar Mahanta House at Khuntapada**

**Block : Patana, Gram Panchayat : Kendeiposi**

**Created By:Soumya Ranjan Behera**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.696	Cubic Meter	240.77592	1130.68372032
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.545	Cubic Meter	705.750832	14499.65084344
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	25.241	Cubic Meter	5948.72626182	150151.7995746
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	15.40875	Cubic Meter	7416.62476234	114280.91680671
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	58.7	Square Meter	216.23489289764	12692.988213091
<b>Total Amount:</b>				292756.03915816
Provision for Contingency (+) @				3000

Display Citizen Board (+) @	3000
Any Other Lumpsum (+) @	1243
Provision for survey investigation and quality control (+) @	

<b>Total Amount:</b>	299999.03915816
----------------------	-----------------

<b>Grand Net Total Amount</b>	299999.03915816
-------------------------------	-----------------

**Soumya Ranjan Behera**  
**JE**  
**Patana Block**

**SUSMITA BEHERA**  
**AEE**  
**Patana Block**

**KendujharPatanaBDO**  
**BDO**  
**Patana Block**