

Estimate Abstract

OD/360/3435/119066/396688/00100590 : CONST OF CC ROAD FROM BISOKA MINI BANK TO KATAKANA PANI TANKI

**Block : Derabish, Gram Panchayat : Khamala
Created By: ABANI KUMAR MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	23.8	Cubic Meter	613.719632	14606.5272416
2	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.05	Cubic Meter	5962.91281676	173222.61732688
3	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	56	Square Meter	216.23489289764	12109.154002268
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	25.55	Cubic Meter	7479.27877712	191095.57275542
5	Earth Work : AR0101aa (Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift) : Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum			
	5.25	Cubic Meter	179.18208	940.70592
Total Amount (A) : 391974.57724616				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.4000	-	4000
2	Display Citizen Board @ Rs.4025	-	4025
Additional Components Amount (F) : 8025			

Grand Total Amount (A + F) : 399999.57724616			
---	--	--	--

ABANI KUMAR MOHANTY
JE
Derabish Block

GOURAV SAHOO
AEE
Derabish Block

Namita Barik
BDO
Derabish Block