

**Estimate Abstract**

**OD/352/3356/117413/402276/00073804 : CONST. OF CC ROAD FROM DALEI SAHI TO RAILWAY  
Block : Parajang, Gram Panchayat : Barihapur  
Created By: Meghlal Mundari**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.6025	Cubic Meter	240.77592	1348.9470918
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.7875	Cubic Meter	651.958232	14204.5399797
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	32.5775	Cubic Meter	5892.29837184	191956.35020862
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	22.72125	Cubic Meter	7321.77381808	166359.85336405
5	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	63.08	Square Meter	216.23489289764	13640.097043983
<b>Total Amount (A) : 387509.78768815</b>				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.4000	-	4000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.3490	Vibrator	3490
<b>Additional Components Amount (F) :</b>			<b>12490</b>

<b>Grand Total Amount (A + F) :</b>			<b>399999.78768815</b>
-------------------------------------	--	--	------------------------

Meghlal Mundari  
JE  
Parajang Block

Rani panda  
AEE  
Parajang Block

Sauvagya Behera  
BDO  
Parajang Block