

Estimate Abstract

**OD/364/3480/119932/430981/00100895 : Laying of Paver Block at Uskapally School Campus
Block : Kalimela, Gram Panchayat : Chitrangapalli
Created By:Bauribandhu parida**

| Sl No | Quantity | Unit | Rate in (Rs.) | Amount (Rs.) |
|---|--|--------------|-----------------|-----------------|
| 1 | Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge | | | |
| | 13.68 | Cubic Meter | 240.77592 | 3293.8145856 |
| 2 | Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge. | | | |
| | 54.72 | Cubic Meter | 778.511232 | 42600.13461504 |
| 3 | Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. | | | |
| | 27.36 | Cubic Meter | 5701.4917534 | 155992.81437302 |
| 4 | R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc | | | |
| | 27.36 | Square Meter | 217.02363744964 | 5937.7667206222 |
| 5 | miscellaneous : ARM286 (Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge. | | | |
| | 547.2 | Square Meter | 520.965 | 285072.048 |
| Total Amount (A) : 492896.57829429 | | | | |

| Additional Components | | | |
|-----------------------|-----------|--------|-----------------|
| # | Item Name | Remark | Amount (in Rs.) |
| | | | |

| | | | |
|--|-------------------------------------|---|------|
| 1 | Provision for Contingency @ Rs.5000 | - | 5000 |
| 2 | Display Citizen Board @ Rs.2100 | - | 2100 |
| Additional Components Amount (F) : 7100 | | | |

| | | | |
|---|--|--|--|
| Grand Total Amount (A + F) : 499996.57829429 | | | |
|---|--|--|--|

**Bauribandhu parida
JE
Kalimela Block**

**Santosh Ku Krisani AEE
AEE
Kalimela Block**

**MalkangiriKalimelaBDO
BDO
Kalimela Block**