

**Estimate Abstract**

**OD/360/3435/119054/396553/00105387 : CONST OF CC ROAD FROM AMAR SAHOO HOUSE TO GOBARI REVIR  
Block : Derabish, Gram Panchayat : Benipur  
Created By:ABANI KUMAR MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	24.475	Cubic Meter	745.221632	18239.2994432
2	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	31.15	Cubic Meter	6026.03377676	187710.95214607
3	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	71.2	Square Meter	216.23489289764	15395.924374312
4	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	26.7	Cubic Meter	7538.45467712	201276.7398791
5	<b>Earth Work : AR0101aa (Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift) :</b> Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum			
	8.9	Cubic Meter	179.18208	1594.720512
				<b>Total Amount (A) : 424217.63635469</b>

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.4320	-	4320
2	Display Citizen Board @ Rs.3462	-	3462
<b>Additional Components Amount (F) : 7782</b>			

<b>Grand Total Amount (A + F) : 431999.63635469</b>			
---	--	--	--

**ABANI KUMAR MOHANTY**  
**JE**  
Derabish Block

**GOURAV SAHOO**  
**AEE**  
Derabish Block

**Namita Barik**  
**BDO**  
Derabish Block