

Estimate Abstract

**OD/353/3357/117448/414643/00067636 : Construction of paver block road at jadimma temple at old kerandi
Block : Gosani, Gram Panchayat : Kerandi
Created By:SURENDRANATH MISHRA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.332	Cubic Meter	5862.66954512	42985.09310482
2	Masonry Brick Work : AR0603b (Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	20.7	Cubic Meter	5337.122559216	110478.43697577
3	miscellaneous : ARM287 (Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.			
	25.2	Square Meter	636.981	16051.9212
4	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.4	Cubic Meter	1019.901232	2447.7629568
5	Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) : 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	180	Square Meter	251.517583504	45273.16503072
6	Iron Work : AR1704 (Iron Doors and windows fixing) : Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.			
	1.05	Quintal	16001.137725087	16801.194611341

7	Flooring : AR0816 (Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor) : Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1 cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.			
	72	Square Meter	1211.6464954146	87238.547669851
Total Amount (A) : 321276.1215493				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	3212.761215493
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.510	unforeseen item	510
Additional Components Amount (F) : 8722.761215493			

Grand Total Amount (A + F) : 329998.8827648			
--	--	--	--

SURENDRANATH MISHRA
JE
Gosani Block

SASMITA KUMARI JENA
AEE
Gosani Block

GOURA CHANDRA PATNAIK
BDO
Gosani Block