

Estimate Abstract

**OD/362/3458/119571/408493/00102407 : Construction of Drain at Ekadalia village
Block : Banapur, Gram Panchayat : Kumarangasana
Created By:PRASANTA KUMAR SAHOO**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	50	Cubic Meter	240.77592	12038.796
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.5	Cubic Meter	1560.907732	11706.80799
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.5	Cubic Meter	6432.6588415	48244.94131125
4	R.C.C. Work : AR0404A (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)			
	21.5	Cubic Meter	6564.368264695	141133.91769094
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	1	Cubic Meter	7834.4199645	7834.4199645
6	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	5.5	Quintal	8656.9325535	47613.12904425

7	R.C.C. Work : AR0410f (Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor in ground floor R.C.C. walls and fins including attached pilasters			
	185	Square Meter	934.29150984209	172843.92932079
Total Amount (A) : 441415.94132173				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Display Citizen Board @ Rs.4000	-	4000
2	Any Other Lumpsum @ Rs.83	Photographs	83
3	Provision for Contingency @ Rs.4500	-	4500
Additional Components Amount (F) : 8583			

Grand Total Amount (A + F) : 449998.94132173

PRASANTA KUMAR SAHOO
JE
Banapur Block

SURESH MALIK
AEE
Banapur Block

Sri Bikash Kumar Mohanty
BDO
Banapur Block