

Estimate Abstract

**OD/346/3302/116141/391598/00106655 : CONSTRUCTION OF CC ROAD FROM PRAMOTH DAS HOUSE TO
BALAI BEHERA HOUSE VILL MANKUNDA
Block : Bhograi, Gram Panchayat : Analia
Created By:SOMANATH MALIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	28.22052288	Cubic Meter	240.77592	6794.8223593131
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.22052288	Cubic Meter	1203.014232	33949.690659122
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	28.22052288	Cubic Meter	7189.25835176	202884.62980607
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	28.22052288	Cubic Meter	8573.36390312	241944.81218656
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	18.51742596	Square Meter	216.39264180804	4007.0347229692
Total Amount (A) : 489580.98973404				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.5000	-	5000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.419	-	419
			Additional Components Amount (F) : 10419

			Grand Total Amount (A + F) : 499999.98973404
--	--	--	--

SOMANATH MALIK
JE
Bhograi Block

PRAMOD KUMAR BEHERA
AEE
Bhograi Block

Prasanta Kumar Moharana
BDO
Bhograi Block